

REPUBLIC OF THE PHILIPPINES
PRESIDENTIAL BROADCAST STAFF-RTVM
MALACANANG, MANILA
TEL : 734-5681

Approved Budget for the Contract: PHP764,400.00

Name of Company

Address:

Gentlemen:

Please quote your lowest price/s for the proposed procurement of good/services as specified hereunder:

ITEM NO.	DESCRIPTION	QTY	SPECIFICATION OF QUOTED ITEM/S	UNIT COST	AMOUNT
1	RENTAL OF THE FOLLOWING FACILITIES/EQUIPMENT TO BE DELIVERED, INSTALLED, TESTED AT RTVM DESIGNATED AREA AT THE BATASAN PAMBANSA.	1 lot			
	1.) 1 unit 20 x 10m x 4m side height Arc Aluminum Closed Tent (profile) Frame Specs- (120mm x 350mm x 6mm) Hard pressed extruded aluminum alloy T6061/T6 Full Glass walls in front and with 2 units main door (20 meters total wide)				
	Requirements:				
	a.) The Aluminum Closed Tent shall have five(5) equally divided rooms and a common dining area.				
	b.) Each room shall have 1-unit 5TR Split type Floor-mounted Aircondition.				
	c.) The Common Dining Area shall have 2-units 5TR Split type Floor-mounted Aircondition.				
	d.) Each room shall be divided with wood panels, with individual door and swags white cloth.				
	e.) Elevation of Flooring is totaled 7½ inches (5 inches beam and 2½ inches flooring) and covered with gray carpet.				
	f.) Fluorescent light shall be provided. (well lighted rooms and dining rooms)				
	g.) Outlet shall be provided in each room.				
	2.) 1lot 10ft x 96ft Tent Walkway with covered flooring(plywood/tubular) and sidings.				
	3.) 1 unit 12ft x 12ft tent for electrical control with covered flooring				
	4.) 2units Silent Type Generator Sets, 150KVA with 12hours fuel, 2lots 75 meters AC cables inclusive of operator to supply power for the Master Control Room; and lights/lighting fixtures and aircon units installed at the Aluminum Closed Tent				
	Requirement:				
	a.) A 1-unit Back-up silent type generator set, 150KVA, with 12hrs fuel, 2lots 75-meters AC cables shall be provided.				
	Terms and Conditions:				
	a.) Set-up time for items 1 to 3 shall start on July 17, 2018 and should be completely installed on or before July 20, 2018. Pull-out of facilities/equipment shall be after the State of the Nation Address on July 23, 2018.				
	b.) Set-up for item 4 and 4a shall be on July 20, 2018. Pull-out time of Generator Sets shall be after the State of the Nation Address on July 23, 2018 upon the advise of the Head for Technical Operation from RTVM.				
	c.) Supplier shall provide for the meals of his employees assigned at the site.				

Very truly yours,


DULCARAMOR QUINTANA
Chairperson, Bids & Awards Committee

THE PROCUREMENT OFFICE-PBS-RTVM

The above price/s is/are our quotation for the goods you wish to procure at your specified period under the following condition:

Delivery Term :

Term of payment :

Price valid for :

Warranty :

.....
Signature Over Printed Name

.....
Designation

Date Quoted